

Workmen climbed up on wooden ladders and scaffolding.

Ropes and pulleys were used to lift the blocks of stone and hoist them into position, one on top of the other. Then they were eased into place with levers.

Carts like this one carried large blocks of stone from the quarry to the building site.

Blocks of stone were joined with pieces of metal called cramps.

